



MAIL BOX PEDESTAL OPENING(S) DETAIL

NOTES:

1. Developer to leave opening (approximately 10" x 10" or 10" dia.) in sidewalk for owner to install post for mailbox. Opening to be filled in with rigid temporary material (i.e. wood or concrete block). Mailbox post not to exceed 8" in diameter.
2. Paired mailboxes to be located maximum 2' apart.
3. The precise locations of mailboxes relative to the lot line may be shifted $\pm 5'$ to avoid conflict with street lights, fire hydrants or driveway approaches (no closer than 4' from such items.).
4. Mailbox locations shall be confirmed by Public Works Inspector prior to installation.
5. Provide 42"-48" clearance from street to bottom of mailbox, and 6" from curb face to front of mailbox.
6. 4' clearance required from mailbox to back of sidewalk (minimum). Sidewalk easement may be required.

				CITY OF THOUSAND OAKS PUBLIC WORKS DEPARTMENT
2	Clarify clearance requirements	3-22-04	<i>AK</i>	
CHG	DESCRIPTION	DATE	INITIAL	STANDARD SIDEWALK MAILBOX EXTENSION DETAILS
APPROVED	<i>Mark White</i> CITY ENGINEER	3/24/04 DATE		