

SECTION 10

WATER SYSTEM AND WORK AREA CLEANUP

10-1 FINAL PROJECT CLEANUP

Once all pipeline systems have been installed, pressure tested, chlorinated and flushed, the system can be field accepted, that is providing the necessary cleanup has occurred. A thorough work area clean up is a prerequisite for field acceptance. All structures including fire hydrants shall be properly painted, where required, and free from dirt, concrete or other spattered materials. The work site will be cleaned of construction debris by the contractor. All private improvements damaged during construction shall be restored to at least the original condition of said improvements including but not limited to lawns, trees, shrubs, curbs, gutters, sidewalks, fences, walls, etc. Filled excavations in private property shall be neatly finished in a manner to facilitate natural drainage and eliminate hazards to persons or property. All requirements of the City and/or County Public Works Department, as appropriate, shall have been met. The project shall be left in a final condition which brings no discredit to the City.