



**NOTES:**

1. PRIOR TO INSTALLATION OF THE METER, A SPACER SHALL BE INSTALLED BETWEEN THE ANGLE METER STOP AND THE CUSTOMER HAND VALVE.
2. SERVICE LINE TO BE LAID FLAT OR AT A POSITIVE SLOPE FROM MAIN.

				<b>CITY OF THOUSAND OAKS</b>	
				PUBLIC WORKS DEPARTMENT	
CHG	DESCRIPTION	DATE	INITIAL	1" WATER SERVICE WITH 3/4" OR 1" METER	
APPROVED	<i>[Signature]</i>	6.10.09			
				PLATE NO. <b>36-2</b>	